

PRODUCERS FISH FEED MILL RENOVATION



Owner

Producers Feed
Company

Size/Capacity

45 tons per hour

Completion Time

8 months

Younglove's Services

- Conceptual design
- Structural engineering
- General construction
- Construction management
- Equipment installation

Isola, Mississippi

This project was done in three phases. Phase 1 was the renovation and addition of the feed loadout driveway. Existing drag conveyors were replaced by belt conveyors and existing screening equipment repositioned. The new loadout equipment is housed in a new steel structure above a new platform scale. Trucks are positioned on the scale and loaded in approximately three minutes with a shuttle (moving) belt conveyor.

Phase 2 work consisted of the removal and replacement of four existing extruders with two larger, more-efficient machines. Phase 3 work consisted of the removal of two existing extruders and replacing them with one new unit. Phase 2 and 3 work included the installation of new screw conveyors and extruders, renovation of the air transfer and cyclone systems, installation of new access platforms, and construction of new control rooms.



YOUNGLOVE

*Builders of value...
Builders of trust*

Leaders in the design and construction of bulk materials handling facilities